

ROOM FINISH SCHEDULE								
NO.	ROOM NAME	FLOOR	BASE	WALL MATERIAL/ FINISH	TRIM	CEILING	CEILING HEIGHT	NOTES AND COMMENTS
100	VESTIBULE	NEW CPT-1	EXIST'G MOBR	CMU - PAINT P-17(C) POLYAMIDE HIGH-BUILD EPOXY. NEW MARLITE WALL PANELS (WP-1) TO 8'-0" AFF, PAINT GYP. BD. P-17(A) ABV WALL PANELS	STAINLESS STEEL CORNERS	GYP BD P-4(D)	9'-10"	FINISH SCHEDULE NOTES 1, 3, & 20
100A	AIRLOCK	NEW CPT-1	EXIST'G MOBR	CMU - PAINT P-17(C) POLYAMIDE HIGH-BUILD EPOXY. NEW MARLITE WALL PANELS (WP-1) TO 8'-0" AFF, PAINT GYP. BD. P-17(A) ABV WALL PANELS	STAINLESS STEEL CORNERS	GYP BD P-4(D)	9'-10"	FINISH SCHEDULE NOTES 1 & 3
100B	AIRLOCK	NEW CPT-1	EXIST'G MOBR	CMU - PAINT P-17(C) POLYAMIDE HIGH-BUILD EPOXY. NEW MARLITE WALL PANELS (WP-1) TO 8'-0" AFF, PAINT GYP. BD. P-17(A) ABV WALL PANELS	STAINLESS STEEL CORNERS	GYP BD P-4(D)	9'-10"	FINISH SCHEDULE NOTES 1 & 3
101	SALES AREA	NEW PERIMETER VCT-2 / EXIST'G FIELD VCT (PATCH & REPAIR)	NEW VB-1	NEW WP-1 TO 8'-0" AFF w/P-17(A) ABOVE UP TO CEILING AT FRONT WALL. NEW WP-1 w/P-13(A) STRIPE & P-17(A) ABOVE UP TO CEILING AT ALL OTHER SALES WALLS. SEE SHEET A2.02	REMOVE - SEE COMMENTS. P-3(B) WHERE APPLICABLE (SAFE TRIM)	EXISTING ACT-1	11'-10"	ALL WOOD TRIM IS TO BE REMOVED. RE: SHEET A2.02 - FINISH SCHEDULE NOTES 1, 3, 5, 7-REFER TO DOOR SCHEDULE, 15, 16, 17, 19, & 20.
102	WORKROOM	NEW VCT-2	NEW VB-1	NEW WP-1 TO 8'-0" AFF ON WALLS WITHOUT SHELVING OR DOOR. PREP AND PAINT REMAINING GYP BD P-17(A) EPOXY FROM FLOOR TO CEILING.	P-3(B) @ SAFE (INSIDE WORK ROOM) & PANEL COVERS	EXISTING ACT-1	11'-10"	FINISH SCHEDULE NOTES #1, 3, 5, 7-REFER TO DOOR SCHEDULE & 16 PAINT VISIBLE WOOD UNDER SHELVES AND COUNTERS P-3(B)
103	SECURITY ROOM	EXIST VCT	EXIST	PAINT CMU P-4 (C) EPOXY	-	EXISTING ACT-1	7'-11"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
104	CORRIDOR	NEW VCT-2	NEW VB-1	NEW WP-1 TO 6" ABOVE EXISTING CEILING SEE: SHEET A2.02	2" BLACK FLEXIBLE BUMPER - TOP @ 32" AFF	EXISTING ACT-1	8'-8"	FINISH SCHEDULE NOTES #1, 3, & 7-REFER TO DOOR SCHEDULE. REPLACE AND/OR ADD NEW STAINLESS STEEL TRIM AS NECESSARY AT EXPOSED CORNERS
105	MEN'S RESTROOM	EXISTING RESINOUS FLOORING	EXIST RESINOUS	EXISTING PWT TO REMAIN - PATCH / REPAIR AS NECESSARY. EXISTING PWT ACCENT BAND TO REMAIN.	-	GYP. BD. P-4(A)	7'-11"	FINISH SCHEDULE NOTES #3, 6, & 7-REFER TO DOOR SCHEDULE. INSTALL NEW STAINLESS STEEL PARTITIONS-SEE SHEET A4.03.
106	WOMEN'S RESTROOM	EXISTING RESINOUS FLOORING	EXIST RESINOUS	EXISTING PWT TO REMAIN - PATCH / REPAIR AS NECESSARY. EXISTING PWT ACCENT BAND TO REMAIN.	-	GYP. BD. P-4(A)	7'-11"	FINISH SCHEDULE NOTES #3, 6, & 7-REFER TO DOOR SCHEDULE. INSTALL NEW STAINLESS STEEL PARTITIONS-SEE SHEET A4.03.
107	RECEIVING ROOM	EXIST CS	EXIST	-	-	EXPOSED STRUCTURE	EXIST	FINISH SCHEDULE NOTE #2,4
108	LOUNGE	EXIST VCT	EXIST	EXIST WALL PANEL - REPLACE / REPAIR DAMAGED PANELS	P-3(B)	EXISTING ACT-1	8'-0"	FINISH SCHEDULE NOTES #1,7-REFER TO DOOR SCHEDULE
109	ASSOCIATE TRAINING ROOM	EXIST VCT	EXIST	EXIST WALL PANEL - REPLACE / REPAIR DAMAGED PANELS	P-3(B)	EXISTING ACT-1	8'-0"	FINISH SCHEDULE NOTES #1,5-NEW SHELF LAMINATE TO MATCH COUNTER LAMINATE, 7-REFER TO DOOR SCHEDULE. PAINT VISIBLE WOOD UNDER SHELVES AND COUNTERS P-3(B).
110	MECHANICAL ROOM #1	EXIST CONCRETE	-	-	-	EXPOSED STRUCTURE	-	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
111	JANITOR'S ROOM	EXIST CONCRETE	-	PAINT CMU P-4 (C) EPOXY	-	GYP. BD./PLYWOOD P-4(B) EPOXY	8'-0"	FINISH SCHEDULE NOTE #7 (REFER TO DOOR SCHEDULE-FRAME ONLY-DOOR REMOVED). CLEAN EXISTING CAN WASH & FLOOR
112	MEAT PREP	EXIST QT	EXIST QTB	EXIST FRP	FACTORY	EXIST ACT-2	10'-0"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
112A	MEAT COOLER	EXIST QT	EXIST QTB	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
112B	MEAT FREEZER	EXIST PREFAB PNL	-	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
112C	TRAY COOLER	EXIST QT	-	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
113	MEAT OFFICE	EXIST QT	EXIST QTB	PAINT CMU P-4(C) EPOXY, DO NOT PAINT MEAT FREEZER WALL	P-4(B) EPOXY	GYP. BD./PLYWOOD P-4(B) EPOXY	8'-0"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
114	DEPT MANAGER'S OFFICE	EXIST VCT	EXIST	EXIST WALL PANEL - REPLACE / REPAIR DAMAGED PANELS	P-3(B)	EXISTING ACT-1	7'-10"	FINISH SCHEDULE NOTES #1,5,7-REFER TO DOOR SCHEDULE. PAINT VISIBLE WOOD UNDER SHELVES AND COUNTERS P-3(B)
115	PRODUCE PREP	EXISTING CONCRETE W/ NEW CONCRETE SEALER	WOOD BASE PAINTED P-4(B)	PAINT CMU P-4(C) EPOXY. REPLACE PAINTED FRP W/ NEW WHITE FRP - UNPAINTED TO REMAIN. PAINT PLND P-4(B)	-	EXIST ACT-2	10'-0"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
115A	PRODUCE COOLER	EXISTING CONCRETE W/ NEW CONCRETE SEALER	EXISTING	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	FINISH SCHEDULE NOTE #2
116	DELI/ BAKERY PREP	EXIST QT	EXIST QTB	EXIST PWT (PATCH & REPAIR); SEE SHEET A2.02.	P-3(B) EPOXY - PANEL COVERS	EXIST ACT-3	8'-7"	RE: SHEET A2.02. PROVIDE METAL CORNER GUARDS TO WALL CORNERS AS REQUIRED.
116A	DELI/ BAKERY COOLER	EXIST QT	EXIST QTB	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	FINISH SCHEDULE NOTE #12
116B	DELI/ BAKERY FREEZER	EXIST MTP	EXISTING	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	FINISH SCHEDULE NOTE #12
117	DELI/ BAKERY CLOSET	EXIST QT	EXIST QTB	EXISTING FRP	-	GYP. BD./PLYWOOD P-4(B) EPOXY	7'-8"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
118	MECHANICAL ROOM #2	EXIST CONCRETE	-	-	-	EXPOSED STRUCTURE	EXIST	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.
119	GROCERY STAGING	EXIST CS	EXISTING	-	-	EXPOSED STRUCTURE	EXIST	FINISH SCHEDULE NOTES #2,4,7-REFER TO DOOR SCHEDULE
120	DAIRY COOLER	EXIST CS	EXISTING	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
121	STORAGE FREEZER	EXIST MTP	FRPB	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
122	ICE CREAM FREEZER	EXIST MTP	FRPB	EXIST PREFAB PNL	-	EXISTING PRE-FAB PANEL	EXIST	
123	RISER ROOM	EXIST CONCRETE	-	EXIST CMU	-	EXISTING GYP. BD.	7'-11"	FINISH SCHEDULE NOTE #7 - REFER TO DOOR SCHEDULE.

GENERAL NOTES:
 1. ALL CONSTRUCTION TO BE TYPE IIB OR BETTER (IBC)
 2. REFER TO SHEET A1.04 FOR ADDITIONAL CEILING INFORMATION.
 3. REFER TO SHEET A2.02 FOR SALES FINISH & A4.03 FOR RESTROOM FINISH LOCATIONS
 4. REFER TO G1.02 FOR NATIONAL ACCOUNT INFORMATION
 5. REPLACE ANY BROKEN/ DAMAGED MATERIALS (ACT, FLOOR/WALL TILE, ETC.) TO MATCH EXISTING UNLESS NEW SPECIFICATION IS LISTED.
 6. DO NOT PAINT POLISHED ALUMINUM TRIM.
 7. REFER TO A1.05 FOR FLOOR FINISHES.

FINISH SCHEDULE NOTES (HYBRID DECOR):
 1. MARLITE BRAND PANELS (MBP): USE TRADITIONAL PROFILE ALUMINUM TRIM PIECES WITH A FACTORY FINISH TO MATCH MARLITE. INSTALL REPLACEMENT MARLITE BRAND PANELS PER MANUFACTURER'S SPECIFICATIONS. USE ONLY ACCEPTABLE MARLITE ACCESSORIES.
 • EXISTING MARLITE PANELING TO REMAIN AND REPAIR AS NEEDED WITH MATCHING PANELS IN NON-CUSTOMER FACING AREAS.
 • EXISTING MARLITE PANELING TO BE REPAIRED AS NEEDED; THEN PAINTED P-2(C) - REFER TO SPECIFICATIONS ON PROPER PRIMER, REPAIR & COATING INSTRUCTIONS.
 • SEE FINISH MATERIAL/COLOR LEGEND FOR NEW MARLITE BRAND PANELS (WP-1) IN SALES AREA, VESTIBULE, WORKROOM, & RESTROOM CORRIDOR.
 2. CAULK 2x6 P.T. WOOD BASEBOARD AT COOLER/FREEZER PANELS & METAL STUD WALLS IN REAR AREA, TOP AND BOTTOM. PAINTED WITH P-4(B).
 3. ALL GYPSUM WALLBOARD TO BE TAPED, MUDDED AND SANDED (PAINT READY)
 4. GENERAL CONTRACTOR SHALL PAINT FIRE LANES IN REAR AREAS, IF REQUIRED.
 5. NEW MILLWORK LAMINATE TO BE FORMICA #889-58 "DESERT BEIGE" MATTE FINISH, REFER TO A4.06. PAINT SUPPORTS P-3(B) U.N.O.
 6. REFER TO A4.04 & A2.02 FOR RESTROOM TILE & DELI-BAKERY TILE.
 7. DOORS AND FRAMES TO BE PAINTED P-3(B), UNLESS OTHERWISE NOTED. (EXCEPT ALLUM. STOREFRONT DOORS & WINDOWS)
 8. ALL WOOD TRIM ADJACENT TO OR CASINGS AROUND DOORS, WINDOWS, TOP OF MARLITE, OPENINGS TO BE PAINTED P-3(B).
 9. ALL WOOD TRIM AT CEILINGS TO BE PAINTED P-17(B).
 10. RESINOUS DECORATIVE FLOORING SHALL BE PURCHASED FROM DUR-A-FLEX INC. (CONTACT: KEVIN STEPHENS 919-208-8662), OR PROTECTIVE INDUSTRIAL POLYMERS (CONTACT: STEVE MCCAMEY AT 804-937-5000).
 11. PROVIDE 1/2" GYP. BD. OVERLAY ON EXISTING CEILING FINISH TAPE, MUD, SAND AND PREP FOR NEW PAINT AS INDICATED. TEMPORARILY UNINSTALL EXISTING LIGHT FIXTURE AS REQUIRED TO INSTALL OVERLAY.
 12. PRE-FAB COOLER/FREEZER PANELS AND DOORS TO BE PAINTED P-3(B); COORDINATE PAINT METHOD W/FOOD LION CONSTRUCTION MANAGER.
 13. COORDINATE WITH FOOD LION CONSTRUCTION MANAGER FOR PAINTING OF WALLS, DOORS & FRAMES.
 14. PROVIDE 4" HIGH FIRE RETARDANT (FRT) PLYWOOD WITH FRT 2X6 WOOD BASE @ EXPOSED COOLER FREEZER WALLS - PAINT BASE PER NOTE #2 AND LEAVE PLYWOOD UNFINISHED.
 15. ALL WALLS BELOW 8' WITHOUT WALL PANELING SHALL BE PAINTED WITH P-17(B) (SEE A2.02).
 16. SAFE AND SAFE TRIM TO BE PAINTED P-3(B) (HAND MACHINE ROLLED NOT BRUSHED).
 17. ALL SALES FLOOR GWB WALLS TO RECEIVE SHERWIN WILLIAMS PROBLOCK OIL BASED PRIMER PRIOR TO PAINTING - SALES FLOOR ONLY.
 18. REMOVE 2X6 WOOD BASE - APPLY RESINOUS FLOORING DIRECTLY TO CMU - FRP AND COOLER WALLS - RESINOUS COVE BASE TO MATCH HEIGHT OF REMOVED WOOD BASE.
 19. SALES AREA COLUMNS TO BE SANDED, PRIMED & PAINTED P-17(B) EPOXY. DO NOT PAINT STAINLESS STEEL WRAPS.
 20. REPLACE WALL PANELS AROUND VESTIBULE COLUMNS, REMOVE HORIZONTAL WOOD TRIM ABV MARLITE WOOD PANELS (WP-1) TO 8'-0" AFF. PAINT GYP. BD ABV P-17(B) UP TO CEILING / DECK. REPLACE STAINLESS STEEL CORNER GUARDS AND INSTALL NEW VB-1 AT BASE OF COLUMNS.

FINISH MATERIAL/COLOR LEGEND:
FLOORS: (SEE SHEETS A1.05 & A4.02 FOR SPECIFIC MATERIALS)
 RESINOUS
 R-1 RESINOUS TOPPING - COLOR FOOD LION #FL106. SEE FINISH SCHEDULE NOTE #10.
 R-2 RESINOUS TOPPING - COLOR FOOD LION #FL106. SEE FINISH SCHEDULE NOTE #10.
 CARPET
 CPT-1 CARPET-PORTICO DIPLOMAT "MINK"
 CPT-2 CARPET- MOHAWK RESTORE "EMERGE #358"
 CPT-3 CARPET- OAK CHARCOAL #4307
 CONCRETE
 CS CONCRETE SEALER
 QUARRY TILE
 QT QUARRY TILE
 PORCELAIN TILE
 PT-1 DAL TILE - REMINISCENT SERIES, "RECLAIMED GRAY" #RM23 UNPOLISHED 12"x12" FLOOR TILE (SEE G9 FOR GROUT DETAILS)
 CERAMIC TILE
 CT-1 DAL TILE - HEATHLAND SERIES, "AMBER HL03" 12"x12" GLAZED CERAMIC FLOOR TILE (SEE G10 FOR GROUT DETAILS)
 VINYL TILE
 VCT-1 VINYL COMPOSITION TILE ARMSTRONG RAFIA-COCOA 55805 12"x24"
 VCT-2 VINYL COMPOSITION TILE- EXCELON IMPERIAL TEXTURE "EARTHSTONE GREIGE" 12"x12"
 VCT-3 VINYL COMPOSITION TILE- EXCELON IMPERIAL TEXTURE "ANTIQUA WHITE" 12"x12"
 OTHER
 WM WALK-OFF MAT-PORTICO SYSTEMS "DIPLOMAT"
 MTP METAL TREAD PLATE
BASE:
 RESINOUS
 R-1 RESINOUS TOPPING, FL105, TURNED UP WALL. SEE SHEET A3.02.
 R-2 RESINOUS TOPPING, FL106, TURNED UP WALL. SEE SHEET A3.02.
 PORCELAIN
 PTB-1 DAL TILE - REMINISCENT SERIES, "MEMENTO WHITE" #RM20 6"x12" (SEE G8 FOR GROUT DETAILS). 12"x12" TILE CUT IN FIELD TO CREATE 6"x12" TILE TO BE USED WITH SCHLUTER DILEX-EHK STAINLESS COVE BASE.
 CERAMIC
 CTB-1 DAL TILE - AFFINITY SERIES, "BEIGE AF02" P-43C9 3"x12" (SEE G7 FOR GROUT DETAILS).
 VINYL
 VB-1 4" VINYL COVE BASE BY JOHNSONITE- MATTE BLACK 40
 OTHER
 MTPB METAL TREAD PLATE BASE
 MOBR MCQUE BOX RAIL
 WD 2x6 P.T. WOOD
CEILING FINISHES: (SEE SHEET A1.04)
 ACT-1 2X4 ARMSTRONG HUMAGUARD PLUS IN PRELUDE XL GRID
 ACT-2 2X4 2" FOAM DOUBLE SIDED FIBERLITE FRP PANEL BY NUDD PRODUCTS
 ACT-3 2X4 ARMSTRONG VINYL CLAD TILE IN PRELUDE XL GRID
 FRP FIBER REINFORCED PANEL
 GB PAINTED GYPSUM BOARD

INTERIOR WALL FINISH PAINTING LEGEND:
 (A) EG-SHEL
 (B) SEMI-GLOSS
 (C) LOW GLOSS
 (D) FLAT
 (E) ELECTROSTATIC

WALLS SURFACES: (REFER TO A2.02 & A4.03)
 CERAMIC WALL TILE
 CWT-1 DAL TILE-"DESERT GRAY" X114 6"x6" SEE (G8) FOR GROUT DETAILS
 CWT-2 DAL TILE-"ARCTIC WHITE" 0190 6"x6" SEE (G3) FOR GROUT DETAILS
 CWT-3 DAL TILE-AFFINITY SERIES "BEIGE AF02" 10x14" SEE (G7) FOR GROUT DETAILS
 CWT-4 DAL TILE-BRIXTON SERIES "MUSHROOM" B033 9"x12" (MATCH EXISTING GROUT)
 CWT-5 DAL TILE-"URBAN PUTTY" 0161 SEMI-GLOSS 4"x12" SEE (G7) FOR GROUT DETAILS
 CWT-6 DAL TILE-"URBAN PUTTY" 0161 MATTE 4"x12" SEE (G7) FOR GROUT DETAILS
 CWT-7 DAL TILE-"ARCHITECTURAL GRAY" 0109 SEMI-GLOSS 6"x6" SEE (G7) FOR GROUT DETAILS
 CWT-8 DAL TILE-"ARTISAN BROWN" 0144 SEMI-GLOSS 1"x6" SEE (G7) FOR GROUT DETAILS
 PORCELAIN WALL TILE
 PWT-1 DAL TILE REMINISCENT SERIES, "MEMENTO WHITE" #RM20 UNPOLISHED 12"x12" WALL TILE (SEE G8 FOR GROUT DETAILS)
 WALL PANELS/COVERING
 WP-1 WHEAT #5347-54 MARLITE PANEL
 WP-2 CODY #194 MARLITE PANEL
 WP-3 LAREDO OAK #324-52 MARLITE PANEL
 WP-4 PLANTATION OAK #323-52 MARLITE PANEL
 WP-5 PAINTABLE WHITE #1001-B02 MARLITE PANEL
 WP-6 MORNING HAZE #5446-52 MARLITE PANEL
 WP-7 PEARL GRAY ACROVYN WALL COVERING
 WP-8 (NOT USED)
 WP-9 WHITE P-100 MARLITE FRP
 WP-10 ALMOND P-118 MARLITE FRP
PAINT: (REFER TO A2.02)
 P-1 PAINT "SOFTER TAN" SW6141
 P-2 PAINT "ELLIE GRAY" SW7650
 P-3 PAINT "MACADAMIA" SW6142
 P-4 PAINT "PURE WHITE" SW7005
 P-5 PAINT "ORGANIC GREEN" SW6732
 P-6 PAINT "GRIZZLE GRAY" SW7068
 P-7 PAINT "MARSHMALLOW" SW7001
 P-8 PAINT "HIGHWAY TRAFFIC WHITE"
 P-9 PAINT "POPULAR GRAY" SW6071
 P-10 PAINT "TINY TAUPE" SW7038
 P-11 PAINT "ENDURING BRONZE" SW7055
 P-12 PAINT "TRAFFIC YELLOW"
 P-13 PAINT "MEDITATIVE" SW6227
 P-14 PAINT "INKWELL" SW6992
 P-15 PAINT "MEGA GREIGE" SW7031
 P-16 PAINT "NEW GRAY" SW7030
 P-17 PAINT "ROMAN COLUMN" SW7562
 P-18 PAINT "SMOKY BEIGE" SW9087
PLASTIC LAMINATE:
 PL-1 WILSONART "CANYON ZEPHYR" (MATTE FINISH)
 PL-2 FORMICA "DESERT BEIGE" (MATTE FINISH)
TRIM:
 ST-1 SCHLUTER- DILEX-EHK EBKH11-011 STAINLESS STEEL COVE BASE
 ST-2 SCHLUTER- RONDEC ROTI00E STAINLESS STEEL TRIM
 ACROVYN
 CR-1 ACROVYN 4000 FR-225N ACCENT RAIL (BLACK)
INTERIOR GROUT FINISH LEGEND:
 (G1) TO USE GROUT: CUSTOM BUILDING PRODUCTS "TRUFFLE" #540
 (G2) TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER GRAY" #386
 (G3) TO USE GROUT: CUSTOM BUILDING PRODUCTS "NEW TAUPE" #185
 (G4) TO USE GROUT: CUSTOM BUILDING PRODUCTS "BONE" #382
 (G5) TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER" #381
 (G6) TO USE GROUT: CUSTOM BUILDING PRODUCTS "NATURAL" #09
 (G7) TO USE GROUT: CUSTOM BUILDING PRODUCTS "LINEN" #122
 (G8) TO USE GROUT: CUSTOM BUILDING PRODUCTS "CAPE GRAY" #546
 (G9) TO USE GROUT: CUSTOM BUILDING PRODUCTS "WINTER GRAY" #355
 (G10) TO USE GROUT: CUSTOM BUILDING PRODUCTS "SAHARA TAN" #22
 NOTE: USE A 1/16" JOINT FOR CERAMIC TILE. USE A 3/16" JOINT FOR PORCELAIN TILE. ALL FLOOR TILE GROUT SHALL BE CEG-IG 100% SOLIDS INDUSTRIAL GRADE EPOXY GROUT BY CUSTOM BUILDING PRODUCTS (COLOR AS INDICATED IN DRAWINGS).



CORPORATE SEAL:

REVISIONS

NO	DATE	REMARKS
1	06/06/06	COMMENTS

END



FOOD LION REMODEL STORE #807
 70 MORGAN SQ, SUITE 11
 BERKELEY SPRINGS, WV

PROJECT NO: 0807FLMK20
 DATE: 02/11/20
 20 OF 48
A6.01
 ROOM FINISH SCHEDULE

CHECKED: A.J.L DRAWN: VPS