



- PLAN NOTES**
- REMOVE & DISPOSE OF PORTION OF EXISTING FLOOR SLAB AS REQUIRED FOR NEW UNDER-SLAB PLUMBING AND/OR REFRIGERATION WORK. COORDINATE EXACT LOCATIONS/AREAS OF REMOVAL W/ PLUMBING AND/OR REFRIGERATION DRAWINGS.
 - REMOVE & DISPOSE OF EXISTING VCT/CARPET/TILE FLOOR FINISH COMPLETE & PREPARE SLAB FOR NEW FINISH PER A1.5/A1.6.

- GENERAL NOTES**
- THIS DRAWING IS PROVIDED FOR INFORMATIONAL/ESTIMATING PURPOSES ONLY. ALL REQUIRED SLAB/PAVING REMOVAL MAY NOT BE INDICATED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW ALL DRAWINGS CAREFULLY INCLUDING ARCHITECTURAL, PLUMBING AND ELECTRICAL FOR MORE INFORMATION ON REQUIREMENTS AND LOCATIONS. THE DIMENSIONS SHOWN SHOULD BE FIELD VERIFIED FOR COORDINATION OF EXISTING CONDITIONS.
 - ALL SLAB CUTTING & PATCHING TO BE PER SPECIFICATION SECTION 030180.
 - UNLESS SHOWN OTHERWISE, ALL TRENCHES ARE TO BE 2'-0" WIDE.
 - COORDINATE TRENCH LOCATIONS AND AREA OF CUT-OUTS WITH PLUMBING DRAWINGS.
 - USE DRILLED HOLES TO CREATE CORNERS OF CUTS. DO NOT OVER-CUT CORNERS.
 - COORDINATE LOCATIONS OF OTHER UNDER-SLAB UTILITIES FROM EXISTING PLANS PRIOR TO WORK AND ALERT OWNER OF ANY POSSIBLE CONFLICTS.
 - PROVIDE STEEL PLATES OVER ANY TRENCHES THAT ARE ACCESSIBLE TO STORE CUSTOMERS OR EMPLOYEES UNTIL ALL WORK FOR THAT TRENCH HAS BEEN COMPLETED.
 - REMOVE AREA OF EXISTING SLAB TO PROVIDE TRENCH FOR NEW REFRIGERATION LINE EXTENSION OFF OF EXISTING LINE. SIZE, LENGTH AND LOCATION TO BE DETERMINED IN FIELD BY CONTRACTOR.
 - THICKNESS OF ALL EXISTING SLABS REQUIRED FOR REMOVAL ARE NOT PRE-DETERMINED & THEREFORE MAY NOT BE GENERAL 4" THICKNESS. CHANGE ORDERS WILL NOT BE ACCEPTED FOR "THICK SLAB" UNLESS IT IS OVER 6" THICK. IF SUCH SLAB IS ENCOUNTERED, THE CONTRACTOR SHALL IDENTIFY EXTENT(S) OF THE THICKENED SLAB AREA(S) PRIOR TO REMOVAL AND OBTAIN A WRITTEN APPROVAL FROM THE KROGER PROJECT MANAGER.
 - LOWER TO ELEVATION EVEN W/ TOP OF SLAB, ALL EXISTING CLEANOUTS THAT OCCUR IN AREAS OF FLOOR FINISH REMOVAL THAT ARE TO HAVE NEW EXPOSED POLISHED CONCRETE.
 - REMOVE ALL FIXTURES AND EQUIPMENT REQUIRED TO COMPLETE VCT/LVT REMOVAL AND FLOOR POLISHING.

LEGEND

	INDICATES AREA OF SLAB REQUIRING REMOVAL
	INDICATES AREA OF FLOOR FINISH REMOVAL

4A DEMOLITION SLAB AND FLOOR FINISHES PLAN
SCALE: 3/32" = 1'-0"

REVISIONS	DATE	DESCRIPTION