



4B CONCRETE PLACEMENT PLAN - MAIN LEVEL
SCALE: 3/8" = 1'-0"

PLAN NOTES

- FURNISH & INSTALL NEW CONCRETE SLAB. SEE A1.6 FOR FLOOR FINISH OR MATCH EXISTING IF NOT OTHERWISE SPECIFIED. WHERE ADJACENT SLAB IS EXPOSED COLORED CONCRETE. COORDINATE EXACT LOCATIONS AND EXTENTS OF WORK FOR EACH AREA WITH ARCHITECTURAL & PLUMBING DRAWINGS.
- FURNISH & INSTALL NEW CONCRETE SLAB. MATCH EXISTING SLOPES OF AND ELEVATIONS OF ADJACENT EDGES TO ACCOMMODATE RESINOUS FINISH & PROVIDE A SMOOTH/FLUSH FINISHED SURFACE W/ ADJACENT FLOOR. SEE A1.6 FOR FLOOR FINISH OR MATCH EXISTING IF NOT OTHERWISE SPECIFIED. COORDINATE EXACT LOCATIONS AND EXTENTS OF WORK FOR EACH AREA WITH ARCHITECTURAL & PLUMBING DRAWINGS.

GENERAL NOTES

- ALL NEW SLABS SHALL BE A MINIMUM OF 4" THICK 3,000 PSI CONCRETE OVER A MINIMUM OF 4" THICK OF POROUS FILL PER SPECIFICATION SECTIONS 030180, 033105 & 033543.
- COORDINATE EXACT LOCATIONS OF ALL NEW INTERIOR FLOOR SLABS W/ SHEETS A01.2, A1.1, A4.1 & PLUMBING SHEETS.
- ALL NEW SLABS SHALL RECEIVE CONTROL JOINTS @ MAX. 12'-0" O.C. EACH WAY. NEW SLABS POURED ADJACENT TO EXISTING SLABS SHALL HAVE JOINT LOCATIONS ALIGN W/ EXISTING ADJACENT LOCATIONS.
- ALL NEW INTERIOR SLABS POURED AGAINST WALLS OR COLUMNS SHALL HAVE A LAYER OF 30# BUILDING FELT FROM BOT. OF POUR UP TO MIN. 6" ABOVE TOP OF SLAB AS BOND BREAK. FELT TO BE TRIMMED DOWN TO TOP OF SLAB AFTER PROPER CURING HAS OCCURRED.
- ALL NEW SLABS POURED AGAINST EXISTING SLABS SHALL BE DOWELED TOGETHER PER ASD-69.

LEGEND

- INDICATES AREA OF NEW SLAB.
- INDICATES AREA OF NEW DEPRESSED SLAB

CAPSTONE
project services, plc

2211 WIDMAN WAY
SUITE 220
FORT MYERS, FL 33901

ARCHITECT

COMMUNITY OF VIRGINIA
JOHN MARK HUGHES
Lic. No. 0401 034169
ARCHITECT

11-29-2021

CAPSTONE
PROJECT SERVICES, PLC

ARCHITECTURAL & CONSTRUCTION SERVICES
OFFICE LOCATIONS: ROANOKE, VA & FT. MYERS, FL

A REMODEL FOR:

KROGER R-327

7805 TIMBERLAKE DRIVE
LYNCHBURG, VA

PROJECT INFO
11-29-2021
DATE CONSTRUCTION SET

CONCRETE
PLACEMENT
PLAN

MARK	DATE	DESCRIPTION

A1.2

SHEET NO.