



- PLAN NOTES**
- NEW SHELVING/END CAPS TO BE FURNISHED BY KROGER AND INSTALLED BY GENERAL CONTRACTOR (G.C.) PER SPEC. SECT. 114113. G.C. TO FURNISH POWER AS REQUIRED PER ELECTRICAL DRAWINGS.
  - NEW FIXTURE TO BE FURNISHED BY KROGER AND INSTALLED BY G.C. PER SPEC. SECT. 114113. NO ELECTRICAL OR PLUMBING WORK REQUIRED.
  - NEW FIXTURE TO BE FURNISHED BY KROGER AND INSTALLED BY G.C. PER SPEC. SECT. 114113. SEE PLUMBING AND/OR ELECTRICAL FOR MORE INFORMATION.
  - NEW FIXTURE TO BE FURNISHED BY KROGER AND INSTALLED BY REFRIGERATION CONTRACTOR (R.C.) PER SPEC. SECT. 114122. SEE PLUMBING, ELECTRICAL AND/OR REFRIGERATION DRAWINGS FOR MORE INFORMATION. G.C. TO COORDINATE.
  - RELOCATED SHELVING/END CAPS TO BE INSTALLED BY G.C. PER SPEC. SECT. 114113. G.C. TO FURNISH POWER AS REQUIRED PER ELECTRICAL DRAWINGS.
  - RELOCATED FIXTURE TO BE INSTALLED BY G.C. PER SPEC. SECT. 114113. NO ELECTRICAL OR PLUMBING WORK REQUIRED.
  - RELOCATED FIXTURE TO BE INSTALLED BY G.C. PER SPEC. SECT. 114113. SEE PLUMBING AND/OR ELECTRICAL FOR MORE INFORMATION.
  - RELOCATED FIXTURE TO BE INSTALLED BY R.C. PER SPEC. SECT. 114122. SEE PLUMBING, ELECTRICAL AND/OR REFRIGERATION DRAWINGS FOR MORE INFORMATION. G.C. TO COORDINATE.
  - FURNISH & INSTALL NEW STAINLESS STEEL CASE CORNER GUARDS PER ASD-160 & SPEC. SECT. 114113-00.
  - FURNISH & INSTALL NEW STAINLESS STEEL REMOVABLE POST CORNER GUARD PER ASD-19 & SPEC. SECT. 114113-00.
  - FURNISH & INSTALL NEW PLASTIC LAMINATE COVERED 3/4" PLYWOOD FILLER AS REQUIRED PER SPEC. SECT. 114113. COVER ALL EXPOSED SURFACES TO PREP ROOM SIDE W/ STAINLESS STEEL PER SPEC. SECTS. 05500 & 114113. FURNISH & INSTALL NEW VINYL BASE TO SURFACES EXPOSED TO SALES FLOOR. SEE PER ASD-510 MATCHING SALES FLOOR. PROVIDE SHOP DRAWINGS TO KROGER P.M. FOR APPROVAL PRIOR TO FABRICATION.
  - FURNISH & INSTALL NEW PLASTIC LAMINATE COVERED 3/4" PLYWOOD FILLER AS REQUIRED PER SPEC. SECT. 114113. FURNISH & INSTALL NEW VINYL BASE TO SURFACES EXPOSED TO SALES FLOOR. SEE PER ASD-510 MATCHING SALES FLOOR. PROVIDE SHOP DRAWINGS TO KROGER P.M. FOR APPROVAL PRIOR TO FABRICATION.
  - RELOCATE EXISTING VENDOR SUPPLIED SANITIZER STATION & SUPPLY WATER AS REQUIRED. SEE PLUMBING DRAWINGS.
  - VENDOR SUPPLIED SANITIZER STATION. CONTRACTOR TO COORDINATE & SUPPLY WATER AS REQUIRED. SEE PLUMBING DRAWINGS.
  - INSTALL NEW KROGER FURNISHED PAPER TOWEL DISPENSER. SEE SPEC. SECT. 102813.
  - INSTALL NEW KROGER FURNISHED SOAP DISPENSER. SEE SPEC. SECT. 102813.
  - INSTALL RELOCATED PAPER TOWEL DISPENSER. SEE SPEC. SECT. 102813.
  - INSTALL RELOCATED SOAP DISPENSER. SEE SPEC. SECT. 102813.
  - OWNER TO FURNISH & INSTALL COMPUTER / TERMINAL / REGISTER / P.O.S. CONTRACTOR TO SUPPLY POWER AS REQUIRED AND COORDINATE INSTALLATION. SEE ELECTRICAL DRAWINGS.
  - FURNISH & INSTALL NEW UTILITY CHASE (6" MTL STUDS WRAPPED W/ 1/2" CYP. RD. SHEATHING ON ALL EXPOSED SURFACES, PAINT TO MATCH ADJACENT DELI BULKHEAD COLOR) FROM TOP OF NEW ADJACENT SHORT WALL UP TO BOTTOM OF EXISTING STEEL ROOF JOISTS ABOVE. SECURE TO STEEL ROOF JOIST(S) W/ UNI-STRUT AS REQUIRED. MODIFY CEILING WHERE PENETRATED. MATCH MATERIALS (FINISHES/SHEATHINGS) AT ADJACENT LOWER WALL LEVEL TO PROVIDE CONTINUATION.
  - INSTALL KROGER FURNISHED REPLACEMENT COUNTER COMPLETE. PROVIDE SHOP DRAWING MEASUREMENT ASSISTANCE TO KROGER P.M. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL REQUIREMENTS.
- GENERAL NOTES**
- INSTALL NEW "ARTISAN" DECOR & DECOR LIGHTING. SEE DECOR DRAWINGS FOR MORE INFORMATION.
  - SEE SHEET A1.1 FOR DOOR SCHEDULE.
  - INSTALL SOLID FRT WOOD BLOCKING IN ALL WALL LOCATIONS WHERE WALL MOUNTED FIXTURES, EQUIPMENT AND/OR ACCESSORIES ARE TO BE LOCATED. INCLUDING BUT NOT EXCLUSIVE TO:  
FLY TRAPPERS AND SCONCES  
IDF RACKS  
WALL DESKS & MARKER BOARDS  
FIRE EXTINGUISHERS  
MILLWORK  
FIRE EXTINGUISHERS
  - INSTALL KROGER FURNISHED FIRE EXTINGUISHERS. COORDINATE LOCATIONS WITH BUILDING OFFICIAL AND FIRE OFFICIAL DURING WALK-THRU PRIOR TO COMPLETION.
  - SEE AS SHEET SERIES FOR ASD & GSD DETAILS.
  - FURNISH NEW BUILDING PLAN STORAGE BOX PER GSD-24. LOCATE AS DIRECTED BY KROGER P.M.
  - PATCH AND REPAIR ALL EXISTING WALLS RECEIVING NEW DECOR FINISHES. FINISHES TO INCLUDE PAINT, WALLPAPER, MARLITE, ETC. INTENT IS TO PROVIDE SMOOTH EVEN FINISH. ALL SURFACES ON SALES FLOOR TO RECEIVE NEW FINISH. SEE DECOR DRAWINGS AND A1.6.

**CAPSTONE project services, plc**  
2211 WIDMAN WAY SUITE 220 FORT MYERS, FL 33901

ARCHITECT

REGISTERED ARCHITECT  
STATE OF FLORIDA  
NO. 10001  
J.M. HUGHES  
11-29-2021

**CAPSTONE PROJECT SERVICES, PLC**  
ARCHITECTURAL & CONSTRUCTION SERVICES  
OFFICE LOCATIONS: ROANOKE, VA & FT. MYERS, FL

**CAPSTONE**

A REMODEL FOR:  
**KROGER R-327**  
7805 TIMBERLAKE DRIVE  
LYNCHBURG, VA

PROJECT NO: 11-29-2021  
DATE: CONSTRUCTION SET

ENLARGED FLOOR PLAN AND DETAILS

SHEET TITLE: A4.1  
REVISIONS:

MARK DATE DESCRIPTION

PROJECT NO: CPS2020-099.4  
CAD DWG FILE: CPS2020-099.4-A4.1  
DRAWN BY: JMH  
CHKD BY: JMH/LEN

**A4.1**

SHEET NO: