PLUMBING LEGEND

SYMBOL/ABBREVIATION	DESCRIPTION
	EXISTING TO BE REMOVED (SHOWN DASHED)
	EXISTING PIPING (SHOWN LIGHT)
	VENT PIPING (V)
	WASTE PIPING (W)
	RISE THRU FLOOR OR ROOF
	DROP OR RISE
	CAPPED PIPE
	WALL CLEANOUT (WCO)
FCO	FLOOR CLEANOUT (FCO)
	HUB DRAIN (HD)
	FLOOR DRAIN (FD)/FLOOR SINK (FS)
A.A.V.	AIR ADMITTANCE VALVE
TD	TRENCH DRAIN
VTR	VENT THROUGH ROOF
	NEW CONNECTION POINT

PLAN NOTES

1. REUSE EXISTING HUB DRAIN FOR NEW CASE. MODIFY AS NEEDED TO MAKE CONNECTION.
2. HUB DRAIN. SEE DETAILS PSD-1 AND PISD-1 ON DRAWING P5.1.
3. EXISTING PIPING TO BE CONNECTED TO WATER CLOSET, PLTLF OR PLTLFH; MODIFY EXISTING PIPING AS NEEDED TO MAKE CONNECTION.
4. EXISTING PIPING TO BE CONNECTED TO URINAL, PLUR. MODIFY EXISTING PIPING AS NEEDED TO MAKE CONNECTION.
5. COUNTERTOP SINK. INSTALL NEW P-TRAP AND INSULATION AND CONNECT TO EXISTING PIPING. SEE DETAIL PSD-50 ON DRAWING P5.1.
6. EXISTING FLOOR DRAIN TO REMAIN FOR NEW CASE CONDENSATE.
7. 2" HUB DRAIN FOR ICE FLAKER, S36TSC-8.
8. RUN DRAIN LINE FROM PRODUCE REVERSE OSMOSIS SYSTEM, PLPROWS, TO FLOOR SINK UNDER 3-COMPARTMENT SINK AND TERMINATE WITH AIR GAP.
9. 3-COMPARTMENT CONDITIONING SINK, PL3-20. SEE DETAIL PSD-7A ON DRAWING P5.1.
10. SEE DETAIL PSD-16B ON DRAWING P5.1 FOR FLOOR SINK, FD-4.
11. 3-COMPARTMENT CLEANING SINK, PL3-20. SEE DETAIL PSD-7 ON DRAWING P5.1.
12. 1-COMPARTMENT SINK, PL1PC-18. SEE DETAIL PSD-5A ON DRAWING P5.1.
13. 2" W AND 1 1/2" V TO HAND SINK, PLHSW AND PLHSSW.
14. 2" W TO FLORAL SINK, PL1F. INSTALL AIR ADMITTANCE VALVE.
15. 2" W AND 1 1/2" V TO HAND SINK, PLHSWE.

NOTE TO CONTRACTOR ON EXISTING CONDITIONS

1. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID AND SURVEY ALL EXISTING CONDITIONS AND EQUIPMENT PRIOR TO SUBMITTING BID FOR WORK REQUIRED BY THESE DOCUMENTS.
2. IF AT ANY TIME THERE IS DISCREPANCY BETWEEN THE PLANS AND SPECS, OR CONFUSION/CONCERN OVER REQUIRED WORK, CONTRACTOR SHALL IMMEDIATELY NOTIFY ARCHITECT, ENGINEER, AND /OR OWNER AND GET DIRECTION BEFORE PROCEEDING WITH WORK IN QUESTION.
3. FOR ALL EXISTING EQUIPMENT TO BE RELOCATED AND OR RE-USED, CONTRACTOR SHALL BE RESPONSIBLE FOR DISCONNECTION, SAFE STORAGE. AND RECONNECTION OF SAID EQUIPMENT COMPLETELY.
4. LOCATIONS OF EXISTING SYSTEMS ARE APPROXIMATE. CONTRACTOR SHALL FIELD VERIFY ALL SYSTEM LOCATIONS PRIOR TO WORK.

4A WASTE AND VENT PLAN

SCALE: 0 4' 8' 16' 24' 32' — 3/32"=1'-0"

6A ELEVATED OFFICES PLAN

SCALE: 0 4' 8' 16' 24' 32' — 3/32"=1'-0"

CAPSTONE
project services, plc
2211 WIDMAN WAY, SUITE 220
FORT MYERS, FL. 33901

COMMONWEALTH OF VIRGINIA
JOHN S. PARKER
Lic. No. 21813
PROFESSIONAL ENGINEER
Digitally Signed
2020.06.01 15:09:16-04'00'
SEAL

NOTE: THIS DOCUMENT MAY HAVE BEEN ELECTRONICALLY TRANSMITTED. IF UNSIGNED, IT CANNOT BE FILED FOR PUBLIC RECORD. PUBLIC RECORD FILINGS REQUIRE SIGNED AND SEALED DOCUMENTS.

BRANDT ENGINEERING, INC.
2949 POLO PARKWAY, SUITE 200
MIDLOTHIAN, VA 23113
PHONE: (804)794-6656
FAX: (804)794-8588
EMAIL: cadd@beiric.com
RICHMOND BRANCH OFFICE
VA PE #: 0309023
CONSULTANT

A REMODEL FOR:
KROGER R-215
7480 LEE HIGHWAY
FAIRLAWN, VA
PROJECT

6-1-2020
DATE
CONSTRUCTION SET

WASTE AND VENT PLAN
SHEET TITLE

REVISIONS		
MARK	DATE	DESCRIPTION

PROJECT NO: 20049
CAD DWG FILE: 20049-P1.1.dwg
DRAWN BY: PC
CHK'D BY: DM/JP

P1.1
SHEET NO.

6/1/2020 1:52:55 PM